



Lake Berryessa Point Seawall Removal 2021 Napa County, CA



Project Information

Prime Contractor:
ROD Construction
P.O. Box 1504
W. Sacramento, CA 95691
(916) 372-5434

Owner:
Bureau of Reclamation
2800 Cottage Way, RM – E-1815
Sacramento, CA 95825

In the early 1960s, a long wooden retaining wall was constructed on the south side of Berryessa Point located in Santa Clara County, California to protect the cove from the wind. Over time, this wooden structure deteriorated and needed to be removed.

ROD Construction was responsible for removing and disposing of all parts of the deteriorated timber seawall and stabilizing the embankment.

Excavators with thumbs were employed for their extended reach and maneuverability within the trench. The removed materials were meticulously sorted into timber and scrap metal and then transported to the nearest disposal sites.

Subsequently, we graded and stabilized the embankment, which comprised dislodged soil, boulders, and other large materials. We employed the hydroseeding method to evenly cover the base ground with grass, thereby preventing soil erosion.

This project restored the integrity of the shoreline and enhanced its resistance to wind and water erosion, ensuring the protection of the cove.

The construction of this project was completed ahead of schedule, on budget, and without a safety incident.

